



17322 Westfield Park Rd.
 P.O. Box 405
 Westfield, IN 46074
 • Phone (317) 896-3700 • Fax (317) 896-9267

PROPOSAL FOR
TOWN OF LAPEL WWTP: WWTP CAMERON CLAUSSEN 705 W Pendleton Ave Lapel, IN 46051-9668 (765)623-0308

PROPOSAL	
Proposal #	9121
Proposal Date	Wed Aug 30, 2023
Proposed By	Keith Hicks
Ship Via	

PROJECT NAME
 Lapel WWTP Influent Flow Meter Repair

Qty	Part #	Name	Description	Rate	Amount
1	604854011	604854011	TIENet™ 350 Ex Area Velocity sensor. 10 ft (3.0 m) measurement range with 75 ft (23 m) cable. Includes one TIENet cord grip fitting (209-0073-12) for watertight sensor cable connection to the Signature® meter in non-conduit applications. The Signature meter must have a desiccator installed for proper operation. Order 604304092 if needed. (604854011)	\$2,240.00	\$2,240.00
1		Installation Services	Professional Installation and Calibration of above 350 sensor.	\$1,850.00	\$1,850.00
1		Shipping 3	SHIPPING	\$53.00	\$53.00
Proposal valid for 30 days from date of issue. Please send P/O number upon acceptance of this proposal to: orders@grippinc.com UPS Ground Shipment Quoted – Overnight Service Available Major Credit Cards Accepted				Sub-Total	\$4,143.00
				Sales Tax	\$0.00
				Total	\$4,143.00

NOTES

Gripp Inc. to provide, install and calibrate a new 350 Area Velocity Sensor at the Influent location, replacing the failed sensor.

CERTIFICATIONS

- Teledyne/Isco Factory Trained Technicians • Confined Space Entry
- CCS • ARSC • ISN • AVETTA • OSHA 10 • WBE

